ODISHA CONSTRUCTION CORPORATION LIMITED

(A GOVT. OF ODISHA UNDERTAKING)

KANUPUR GATE ERECTION PROJECT

BASUDEVPUR,KEONJHAR.

GSTIN-21AAACO2571K2ZM

DESIGNED TO EXCEL

TENDER DOCUMENT

Tender Call Notice No.OCCL/KGEP/ 07 /2026-27 Dated 16.11.2026

Name of work:

Electrical arrangement for power supply & operation of 02 Nos. of Service gates and 02 Nos. of Emergency gates including lighting arrangements pertaining to Depletion Sluice of Kanupur Gate Erection Project, Basudevpur, Keonjhar as per the direction of Engineer-in-Charge.

(This tender document contains 19 (Nineteen) sheets including this cover page)

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

OFFICE OF THE SENIOR MANAGER (MECH.),
ODISHA CONSTRUCTION CORPORATION LIMITED,
(A GOVT. OF ODISHA UNDERTAKING)
KANUPUR GATE ERECTION PROJECT,
BASUDEVPUR,KEONJAR

****

TENDER CALL NOTICE NO. OCCL/ KGEP/ 07 /2026-27 dated 16.11.2026

1. On behalf of M/s. Odisha Construction Corporation Ltd, ("OCCL"), Senior Manager (Mech.), Kanupur Gate Erection Project, Basudevpur,Keonjhar (Odisha) invites sealed Tenders from the interested reputed Electrical Contractors enlisted in OCCL having MV / HT license with relevant experience on MV/ HT erection and installation work for the following items / works.

Sl. No.	Description of Items/works	Cost of tender document + CGST @ 9% +SGST @ 9% (in ₹)	EMD (in Rs.) Excluding GST	Period of completion.	Class of tenderer
1	Electrical arrangement for power supply & operation of 02 Nos. of Service gates and 02 Nos. of Emergency gates including lighting arrangements pertaining to Depletion Sluice of Kanupur Gate Erection Project, Basudevpur, Keonjhar as per the direction of Engineer-in-Charge	7,080-(Non-refundable)	Rs.10,513/-	30 (Thirty) days	Electrical Contractor enlisted in OCCL having MV / HT license

2. The tender document may be downloaded from OCCL website www.odishaconstruction.com and non-refundable cost of tender document amounting to Rs. 7,080/- (Rupees Seven thousand Eighty) only inclusive of CGST @ 9 % & SGST @ 9% in shape of Account Payee Demand Draft drawn on any Nationalised / Scheduled Bank payable at Bileipada only in favour of "Odisha Construction Corporation Ltd. - Project Account ". Interested Job-workers may obtain further information, if any, from the undersigned".
3. The Tender must be accompanied with Earnest Money Deposit (EMD) value of ₹. 10,513.00 (Ten thousand Five hundred Thirteen) only in shape of N.S.C. / Post Office Saving Bank Account / Post Office Time Deposit Account / Kisan Vikas Patra / Bank Guarantee / TDR / FDR in favour of Odisha Construction Corporation Limited from any Nationalized Scheduled Bank in India counter guaranteed by its local branch at Bileipada / e-Bank guarantee executed on the National e- Governance services limited (NeSL) Digital Document Executed Portal / in shape of account payee Demand Draft drawn on any Nationalized / Scheduled Bank payable at Bileipada only in favour of "Odisha Construction Corporation Ltd. - Project Account.
4. Tender documents received without Earnest Money Deposit (EMD) & cost of tender documents will be out rightly rejected. **Tender documents will be received through password protected e-mail (E-mail:-smmechkanupur@gmail.com) Password shall be revealed or intimated by the bidder at the time of opening of price bid documents**.

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal
,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

5. The tender document must be submitted through e-mail on or before 3.00 PM on 21.11.2026 and will be opened on 21.11.2026 at 4.00 PM in the presence of the bidders, who may like to be present. The bids can only be opened by the pre-designated officials only after the opening time mentioned in the bid. In the event of the specified date of bid opening being declared a holiday, the bid will be opened at the same time and same venue in the next working day.

6. Intending Job-Workers are required to furnish the following documents along with their tender.

(i) Complete tender document duly filled in and signed on each page by the Job-Worker or his/their power of Attorney holder with date, full name, Designation, & Official Seal. In case of power of Attorney holder the copy of such delegation is to be enclosed with the tender documents. Power of Attorney to be executed on non-judicial stamp paper of the appropriate value in accordance with relevant Stamp Act. The stamp paper to be in the name of the Job-Worker who is issuing the Power of Attorney

(ii) Cost of tender document **(Annexure - A)**

(iii) Earnest Money Deposit (EMD) in enclosed format **(Annexure-B)**

(iv) Copy of valid GST certificate.

(v) Copy of valid registration certificate issued by Provident Fund Authority.

(vi) Copy of valid ESI registration certificate issued by competent authorities.

(vii) Copy of PAN card

(viii) Undertakings in prescribed available in tender document **(Annexure-F)** & **(Annexure-G)**.

(ix) Copy of valid electrical enlistment certificate as Job-Worker issued by "OCC Ltd."

(x) Structure and organization(**Annexure-C**), No Relation Certificate (**Annexure-E**)

(xi) Affidavit duly registered before NOTARY regarding authenticity of documents (**Annexure-D**).

(xiii) Copies of documents on credentials in support of execution of similar nature of work.

7. The tender document should be submitted only through e-mail (smmechkanupur@gmail.com) within stipulated date and time. No other mode will be accepted other than e-mail (smmechkanupur@gmail.com) to receive the tender documents by this office. The undersigned will not be responsible for any kind of delay by the technical issue**.**

The tenderer who will participate through e-mail(smmechkanupur@gmail.com) must upload all the self attested technical bid documents in Enclosure. The tender participated through e-mail will scan the tender & EMD cost document / relevant financial documents and upload the same along with tender document in enclosure. Subject of the e-mail should be "Electrical arrangement for power supply & operation of 02 Nos. of Service gates and 02 Nos. of Emergency gates including lighting arrangements pertaining to Depletion Sluice of Kanupur Gate Erection Project, Basudevpur, Keonjhar as per the direction of Engineer-in-Charge". Original copy of tender and EMD cost must submitted to the undersigned within 07 (Seven) working days.

8. The Job-Worker registered under NSIC / MSME for participation in tender / quotation are not entitled for exemption from payment of EMD / Security Deposit / Tender paper cost / quotation paper cost as per provision exist in O.P.W.D code and amended by Govt. of Odisha, Department of Water Resources.

9. The authority reserves absolute right to accept or reject any or all tenders without assigning any reason thereof.

10. The intending bidder(s) is / are to quote their rates in the enclosed blank price schedule format.

11. The successful bidder shall have to execute the work as per scope of work, relevant drawings, technical specifications, terms and conditions of agreement.

12. Quantity may increase or decrease as per requirement during execution of work at site as per direction of Engineer-in-charge.

13. The tenderer should furnish detailed rate analysis of the work enclosing price list of materials to be supplied with make & authorisations of reputed manufacturers for the work along with the tender.

14. The validity of offer should be for a period of **90**(Ninety)days from the date of opening of tenders.OCC Ltd. may be asked further extension of validity if required without any price rise.

15. Any dispute arising out of this tender or order thereof is to be settled in proper court under the jurisdiction of Odisha High Court at Cuttack or Courts at Bhubaneswar only under the jurisdiction of Odisha High Court.

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

ANNEXURE – A

TENDER PAPER COST AND DOCUMENT DEPOSIT PARTICULARS

1. Cost of Tender Rs. **7,080** /- (Rupees Seven thousand Eighty) only vide Demand Draft No._____ in any nationalized bank / scheduled bank _____ Dated _____ issued by _____ Bank, _____ Branch _____

2. GST Registration Certificate

3. P.A.N. card

4. Names of relations in O.C.C. Ltd.

5. Any other documents.

Full signature of "Job-worker" with date and seal

.

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

ANNEXURE - B

DETAILS OF EARNEST MONEY DEPOSIT (EMD) AND DOCUMENTS SUBMITTED ALONG WITH TENDER

1. EMD amount ₹._____(Rupees_____) only in shape of N.S.C. / Post Office Saving Bank Account / Post Office Time Deposit Account / Kisan Vikas Patra / Bank Guarantee / TDR / FDR No. _____Dated _____ issued by Bank,_____Branch _____.

2. GST Registration Certificate

3. P.A.N. card

4. Names of relations in O.C.C. Ltd.

5. Any other documents.

Full signature of "Job-Worker"
with date and seal

Company Name.....

:

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

ANNEXURE - C

FORM – A

STRUCTURE AND ORGANISATION

1. Name of Job-Worker .....
2. Nationality of Job-Worker .....
3. Office Address
   .....
   .....
   .....
   .....
4. Telephone No.
   Land phone .....
   Mobile.....
   Fax No.....
5. E-mail id .....
   .....
6. Location of establishment .....
   .....
7. The Job-Worker is

a. An individual

b. A proprietary firm

c. A limited company or limited corporation

d . A member of a group of companies (If yes, give names, address and present description of other companies.

e. A subsidiary of large organization

(If yes, give names, address of the present organization)

f. If the company is subsidiary state what involvement if any, will the parent company have in the project.

Attach the organization chart showing the structure of the organization including the names of the Directors position of officer.

8. Number of year of experience

a. As a prime Contractor

b. I In own country

II Other country (specify country)

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

ANNEXURE - D

(AFFIDAVIT)

(To be submitted in original in legal stamp paper duly registered)

1. The undersigned hereby certifies that, all the statements made in the required attachments are true and correct. If any of the documents submitted by us is found to be false and fabricated, then appropriate action as deemed fit as per the law of land may be initiated against us.

2 The undersigned also hereby certify that, neither our firm _____ nor any of its construction partners have abandoned any ELECTRICAL or other project work in India nor any contract awarded to us for such works have been rescinded during the last five years prior to the date of this tender.

3 The undersigned hereby authorized and request (s) bank, firm or Corporation to furnish pertinent information as deemed necessary and as requested by the Corporation to verify this statement or regarding my (our) competency and general reputation.

4 The undersigned understands and agrees that further qualifying information may be requested and agree to furnish any such information at the request of the Corporation.

(Signed by an Authorized of the firm)
Title of Officer
Name of Firm
Date

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal
,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

ANNEXURE - E

CERTIFICATE OF NO-RELATIONSHIP

I/We hereby certify that I/We am/are not related to any officer of Govt. of Odisha / OCC Ltd of the rank of Asst. Executive Engineer and above and any officer of the rank of Under Secretary and above in the W.R. Department. I/We am/are aware that if the facts subsequently proved to be false my/our contract will be rescinded with forfeiture of EMD & security deposit and I/We shall be liable to make good the loss or damage resulting from such cancellation.

I/We also note that, non- submission of this certificate will render my/our tender liable for rejection.

Signature of the Job-Worker

Name:

Address

_____

Date :

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

ANNEXURE - F

UNDERTAKING TO PAY MINIMUM WAGES

I / We do hereby undertake that, we shall pay wages of each labour at the rate not less than the wages as per Minimum Wages Act in force during the time of execution and as may be amended from time to time. The "Engineer-in-Charge" has the right to enquire into and decide on any complaint of the Labourers relating to non-payment or less payment of wages to them and his decision will be final and binding on us.

Signature of the Job-Worker

Name _____

Address _____

_____

Date : _____

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

ANNEXURE - G

Undertaking of Job-Worker

I / We Sri

(In case of the firm, the name of the proprietor/head of the firm along with the designation & name of firm should be mentioned)

S/o:- Sri _____, Permanent resident of

Vill/Street:-_____, P.O.- _____,P.S.- _____

Via: - _____ , Dist.- _____

State: - _____, PIN: -_____

declare that I/We have thoroughly gone through the Tender document and I/We know the sites of works. I/We agree to work at rates quoted by me/us or at settled rates and abide by the terms and conditions of the Tender document.

Full signature of "Job-Worker"
with date and seal.
Present address for correspondence

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

SCOPE OF WORK FOR ELECTRICAL CONTRACTOR

1) The Job-worker has to supply all required electrical, Mechanical etc. items as per BOQ to complete the electrification, trial, testing & commissioning of the work; "Electrical arrangement for power supply & operation of 02 Nos. of Service gates and 02 Nos. of Emergency gates including lighting arrangements pertaining to Depletion Sluice of Kanupur Gate Erection Project, Basudevpur, Keonjhar as per the direction of Engineer-in-Charge."

2) The tenderer has to supply all switch gears, MCCBs and reversible starters of reputed manufacturer like L & T, Havells, BCH, Simens or any other ISI marked.

3) The tenderer has to supply the power cables of reputed make (KEI / Havells / Polycab / any other reputed make) certificates as per IS code and as per enclosed price schedule.

4) Electricity shall be supplied by OCCL at single point.

5) Welding machine required for welding purpose shall be supplied by the OCCL.

6) All the materials will be inspected by Engineer-in-Charge / or his authorized representative before despatch on prior intimation.

7) Electrical materials transportation including loading & unloading shall be borne by the Job-worker at his own cost.

8) Security of the materials till handing over the work shall be under the scope of the Job-worker.

9) Rest shed, drinking water, etc. will be arranged by the Job-worker at his own cost

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal
,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

GENERAL TERMS AND CONDITIONS

1. **DEFINITIONS**:

i) "CORPORATION" means "ODISHA CONSTRUCTION CORPORATION LTD, ("OCCL" in short)" with registered office at Unit – VIII, Gopabandhu Nagar, Bhubaneswar-751012 (Odisha) represented through its Managing Director or any other officer as designated by the "Corporation" from time to time.

ii) "**ENGINEER-IN-CHARGE**" means the qualified Engineer deployed by the "Corporation" at work site for the work including the Senior Manager (Mech.) / Manager / Asst. Manager (Elect.), Asst. Manager (Mech.) "OCCL".

iii) "**CONTRACTOR**" means the person / firm / organization i.e. reputed Electrical Contractor enlisted in OCC Ltd. having MV / HT license / Registered Electrical Firm having relevant experience on MV / HT erection and installation work, subsequent technical person, machinery, materials etc. have been awarded by OCCL to execute the work satisfactorily as per scope indicated herein within stipulated period.

2. **AGREEMENT**:

The "**Contractor**" shall enter into an agreement with the "Engineer-in-Charge" in the format on requisite value of stamp paper prescribed for the purpose by the "Corporation" within a stipulated period to be specified by the "Engineer-in-Charge" failing which the EMD and ISD shall be forfeited. The work may be awarded in favour of some other agency at the discretion of the "Corporation".

3. **CONDITIONS FOR SUPPLY ITEMS.**

i) The tender shall quote their rates **F.O.R. Odisha Construction Corporation Ltd., Lower Suktel Gate Erection Project, At: Magurbeda, Dist: Balangir** inclusive of all levies, duties, transportation, transit insurance, excluding GST etc.

ii) The material should be guaranteed against any manufacturing defects for a period of one year from the date of operation/ installation whichever is earlier. Materials if found defective within the guarantee period, the same shall have to be replaced free of cost by the supplier.

iii) Materials to be supplied shall be strictly as per proper specification & applicable make should be clearly mentioned against each item. In case of any doubt on the item the tenderer/supplier may contact the undersigned for confirmation before quoting rate.

iv) The validity of the offer should be for a period of **90** (Ninety) **days** from the date of opening of the tender.

v) The complete order shall have to be executed within **30** (Thirty) **days** from the date of issue of the work order failing which the order is liable for cancellation. In case of any delay in supply of material beyond the delivery schedule whatever may the reason, supplier shall be liable to pay L.D. @ 0.5%(half percent) of the total work value of delay or part thereof subject to a maximum of 5% (five percent) of the total work value.

vi) The Job-worker shall have provided circuit diagram of his assembled unit, all test certificate and warranty cards, purchase bills etc. for reference of OCCL.

4. **RATE**:

The rate quoted by the tenderer is to be indicated in Rupees, which shall be valid for the full period of execution or till completion of work whichever is later. No escalation or price variation in whatsoever form shall be entertained. The rates quoted by the tenderer should be firm for the entire period of execution. The tenderer shall quote the rates to complete the works as per specifications inclusive of all transportation, handling, loading, unloading, lift, de-lift, taxes, duties, levies, incidental expenses etc. that will be applicable on the work to be executed by him. No claim in this regard in whatsoever form shall be entertained.

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

5. **PAYMENT TERMS**:

a. No advance, price escalation and price adjustment shall be paid for the work. The rates shall remain firm throughout the agreement period.

b. The payment to the "**Contracto**r" shall be limited to the measurements taken and accepted by the client. The "Contractor" cannot raise any dispute over the measurements allowed by the "Engineer-in-Charge" for the purpose of payment.

c. The Contractor will bear the full cost of rectification or replacement of works required as per direction of "Client" or "Engineer-in-Charge".

d. 70% of value towards cost of materials shall be made within 30(thirty) days after receipt, verification and acceptance of the complete materials along with bill, test certificate, guarantee certificate and other documents at the work site. Balance 20% towards cost of materials transportation and erection, electrical installation, testing and commissioning shall be made within 30(thirty) days after successful erection, electrical installation, testing & commissioning. Balance 10% of total work cost shall be released within 60(sixty) days against receipt of Performance Bank Guarantee (PBG) for 10% value of total work cost(basic) valid for 18(eighteen) months from the date of successful erection, electrical installation, testing & commissioning. In absence of PBG, balance 10% value of total work cost shall be released after 18 months of successful erection, electrical installation, testing & commissioning.

6. **INCOME TAX, GST ETC**. :

Income Tax at the prevailing rate from time to time will be deducted from each bill of the "**Contracto**r" and shall be deposited with Income Tax Authorities. The **Contracto**r will have to produce tax invoice against each bill for payment.

7) **RETURN OF PLANT, MACHINERY, EQUIPMENTS, TOOLS, TACKLES, MATERIALS, CONSUMABLES ETC.**:

The plants, machinery, equipments etc. of the "Corporation" are to be returned by the "**Contracto**r" in good working condition after completion of the work/termination of the contract by the "Corporation". The "Corporation" may hire plants, machinery, equipments, etc. from the owner as well as outside for use in work. The same are also to be returned by the "**Contracto**r" in acceptable good working condition with original fittings after completion of the work/termination of the contract by the "Corporation".

Any damage to/ by the plants, machinery, equipments etc. during use by the "**Contracto**r" shall be booked to the "**Contracto**r" for recovery from his bills.

8) **MEASUREMENT OF WORK**:

The quantity of work executed shall be measured and payment shall be made on completion of work or on termination of the agreement, when final measurement will be made and account will be adjusted accordingly. The decision of the "Engineer-in-Charge" regarding the rates, progress, measurement and quality of the work shall be final and binding on the "Contractor".

9) **ELECTRICITY**

Electricity if required for execution of work shall be provided by the Corporation and/or owner free of charges at one point only from where the contractor shall arrange further distribution with his own materials and labour.

10) **PAYMENT TO WORKMEN**:

The "Contracor" should maintain job register and payment rolls of their workmen and get those checked by the "Engineer-in-Charge" or his authorized representative from time to time. The payment to the workers/ supervisory staff shall be made by the "Contractor" in the presence of the owner and/or "Engineer-in-Charge" or his authorized representative as a token of disbursement.

The copies of paid pay roll shall be submitted to the "Engineer-in-Charge" within a period of 7 (Seven) days from the date of payment failing which no further payment to the "**Contracto**r" shall be released.

11) **WORKMEN COMPENSATION**:
In case of any loss due to accident arising during / in connection with execution of the contract, the "Contractor" will pay compensation to his workmen. The "Contractor" will be fully responsible for his workmen as per workmen's compensation Act and Labour Laws in force during entire period of execution of contract. In case, the "Contractor" fails to do so, the "Corporation" may pay the same and recover the same from the bills / dues of the "Contractor".

12) **INFORMATION OF WORKMEN**:
The "Contractor" will make his own arrangements of labour and shall furnish all information of workmen employed by him like name, father's name, full permanent address, sex and age to the "Engineer-in-Charge" along with the pay.

13) **STATUTORY REQUIREMENTS**:
The "Contractor" shall comply all statutory requirements applicable at site of work such as Minimum Wage Act, Labour Act, Factory Act, Workmen's Compensation Act, Provident Fund Rules, etc. A certificate to this effect shall be enclosed by the "Contractor" with each Running Account Bill for payment.

14) **MINIMUM AGE OF WORKMEN**:
The "Contractor" shall not employ any person, who is below the age of 18 (Eighteen) years or unfit for the tendered items. The "Engineer-in-Charge" shall have right to decide, whether any labour employed by the "Contracftor" is below the age of 18 (Eighteen) years or unfit and refuse to allow any labour, whom he decides to be below the age of 18 years or unfit for any other reason.

15) **LABOUR LICENCE**:
The "Contractor" has to obtain valid labour license and maintain all records at his own cost as per the conditions laid down in the labour rules in vogue and amended from time to time.

16) **MINIMUM WAGES ACT**:
The "Contractor" shall pay wages of each labour at the rate not less than the wages as per Minimum Wages Act in force and as may be amended from time to time. The "Engineer-in-Charge" has the right to enquire into and decide on any complaint of the labourers relating to non-payment or less payment of wages to them and his decision will be final and binding on the "Job-worker".

17) **INSURANCE**:
The workmen insurance shall be the responsibility of the "Contractor". He shall produce the records in support of workmen insurance to the "Engineer-in-Charge" for check and record. Further the materials supplied and work executed shall be fully insured by supplier under compressive insurance policy covering all risk against loss or damaged incidental manufacturer or acquisition, transportation, storage execution and till acceptance/handing over of the completed work.

18) **IDLE LABOUR**:
"OCCL" will not be held responsible for idle labourers of the "**Contracto**r" for any reason, whatsoever and no claim on this account will be entertained.

19) **CLAIMS AND LIABILITIES**:
All claims/liabilities etc. arising out of Explosives Act and Labour laws shall be borne by the "Contractor" and he shall keep the "Corporation" indemnified against them and also in case of injuries or death of labourer (s) resulting from accidents during the execution of the work. In case

the "Corporation" will have to pay for any such claims under Workmen's Compensation Act, the same shall be adjusted from the pending bills/dues of the "Contractor" or shall be recovered otherwise as per law from him.

20) **SAFETY**:
The "Contractor" should abide by the safety laws and rules of statutory bodies, "Corporation" and owner as per direction of "Engineer-in-Charge" and Safety Officers inspecting from time to time.

21) **WATCH AND WARD**:
The "Contractor" shall arrange watch and ward and safety of the site his materials, vehicles, equipments, etc. at his own cost. No accommodation will be provided by OCCL. The **Contractor** has to arrange accommodation for their working staff during execution of work as well as proper shed for storage of materials with safety precautions.

22) **AUTHORISED PERSON**:
The "Contractor" may in writing authorize his power of attorney holder or any other person to draw materials, avail facilities, attend measurements etc. during the course of execution of work. All liabilities created by the authorized person of the "Contractor" by way of loss of materials drawn, amenities availed, unpaid wages created etc. shall be considered as the liabilities of the Job worker and such liabilities shall be made good by the "Contractor" or it shall be recovered from the bill/payment due to him.

23) **RESPONSIBILITY OF CONTRACTOR**:
The work shall be completed by the "Contractor" in all respect within the stipulated period of completion and the responsibility of the "Contractor" shall cease only, when the items are fully accepted by the owner after erection at project site.

24) **REJECTION DUE TO BAD WORKMANSHIP**:
The rejection due to bad workmanship shall be charged to the "Contractor" at a cost of rejected items plus 20 (Twenty) %.

25) **BREACH OF CONTRACT**:
The ISD including EMD, SD and additional SD are liable to be forfeited in the event of breach of contract and the agreement shall be terminated. The dues of the "Corporation" including due of labourers/ workmen and other statutory payable liabilities payable by the "Corporation" as principal employer shall be cleared by the "**Contractor**". The decision of the "Engineer-in-Charge" in this regard shall be final and binding on the "Contractor". The amount remaining as outstanding against the "Contractor" after adjustment of his dues shall be payable by him to "OCCL". If necessary, legal action may be taken for recovery of the dues of the "Corporation" including labour and statutory dues to be cleared by the "Corporation" as principal employer and "OCCL" reserves the right to recover the payable amount from the "Contractor" from works done by his under any other organization or from his properties.

26) **TERMINATION OF CONTRACT**:
The "Engineer-in-Charge" may put an end to the agreement at his option at any time due to (a) Bad workmanship (b) Dis-proportionate progress (c) Non-compliance of labour rules or (d) Any other reason. The decision of the "Engineer-in-Charge" is final in this respect and no claim on this account will be entertained. "OCCL" also reserves the right to take exparte measurements, if the "Contractor" does not co-operate in taking final measurements after termination of contract.

27) **SITE VISIT**:
The "Contractor", interested to participate in the tender, should visit the site of work and get himself acquainted with site conditions and tendered work before submitting the tender.

28) **RIGHT OF THE "CORPORATION**":
The "Corporation" reserves the right to cancel a particular tender call or all tender calls without assigning any reason thereof. The offer of any tenderer or all may be cancelled without assigning any reason thereof. **The requirement shown in any tender call notice are only indicative and may vary**.

29) **FORCE MEASURE**:
Neither party shall be liable to the other for any loss or damage occasioned by or arising out of acts of God such as unprecedented flood, volcanic eruption, earthquake or other convulsion of nature and other acts such as but not restricted to invasion, the act of foreign countries, hostilities, or war-like operations before or after declaration of war, rebellion, military or usurped power which prevent performance of the contract and which could not be foreseen or avoided by a prudent person.

30) **JURISDICTION**:
For all liabilities created under the various contractual obligations/impositions under this agreement, the "Contractor" undertakes not to raise any dispute or litigations in connection there with and shall make all endeavors to resolve all disputes amicably through conciliation and in all such cases, the decision of the Managing Director, "OCCL" shall be final and binding on the "Corporation" as well as on the "Contractor" failing which all such disputes arising out of the agreement shall be subject to jurisdiction of Hon'ble High Court of Odisha at Cuttack and their sub-ordinate courts at Bhubaneswar only. Both the parties agree by mutual consent that any dispute relating to this agreement is barred from arbitration.

****

OFFICE OF THE SENIOR MANAGER (MECH.),
KANUPUR GATE ERECTION PROJECT,
ODISHA CONSTRUCTION CORPORATION LTD.
(A GOVERNMENT OF ODISHA UNDERTAKING)
BASUDEVPUR, KEONJHAR
****

BILL OF QUANTITY

For the work; " Electrical arrangement for power supply & operation of 02 Nos. of Service gates and 02 Nos. of Emergency gates including lighting arrangements pertaining to Depletion Sluice of Kanupur Gate Erection Project, Basudevpur, Keonjhar as per the direction of Engineer-in-Charge"

vide tender call notice No.**OCCL/KGEP/ 07 /2026-27 dated 16.11.2026**

Sl. No.	Description of Items	Unit	Qnty.	Basic rate Without GST in Rs.	Total Amount (Without GST)	
					In Rs	In words
1	Supply, installation, testing & commissioning of L.T. outdoor with slanting roof floor mounted type **Main Panel** made out of 2mm thick CRCA sheet metal, cubical fixed on M.S. angle frame work, duly acid treated for derusting, premiered and painted with 2 coats of enamel paints of approved shade; IP-52 class of protection, having hinged door with provision for cable / conduit entry and earthing studs, as per specification mentioned below duly factory wired conforming to the relevant ISS and as per special conditions of contact making good the damages caused complete as per the direction of Engineer-in-charge. ***Incoming*** 01 no. 250 Amp TPN on load change over switch. 01 no. 250 Amp FP MCCB (25 KA) 1 Set 300 Amp TPN Cu Bus. ***Outgoing*** 05 nos. 63 Amp FP MCCB (25 KA) 01 no. 32 Amp FP MCCB (25 KA) Instrument - 1 set of phase indicating lamp with control fuses, Voltmeter, Ammiter with selector switch, and C.T. etc.	Set	01			

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project

Sl. No.	Description of Items	Unit	Qnty.	Basic rate Without GST in Rs.	Total Amount (Without GST)	
					In Rs	In words
2	Supply, installation, testing & commissioning of Reversing starter in a slanting roof enclosure for 11 KW / 15 HP induction motor with single phase preventer and over load relay for Depletion Sluice Service & emergency gates as per direction of Engineer-in- Charge.	Nos.	04			
3	Supply, lying, testing & commissioning of following size of PVC insulated, PVC sheathead, GI round / strip armored stranded conductor power cable of 1100 volt grade conforming to IS:1554/1978 amended up to date, including the cost of cable end termination, Glanding etc. complete with making good the damages caused as required and as per direction of Engineer-in-charge.					
	(A) 3.5 C 95 Sqmm Al. Arm. Cable	Mtr.	120			
	(B) 4 C 6 Sqmm Al. Arm. Cable	Mtr.	200			
	(C) 4 C 6 Sqmm flexible Cu cable	Mtr.	100			
	(D) 3 C 6 Sqmm flexible Cu cable	Mtr.	100			
	(E) 2.5 Sqmm Cu Multi Core wire	Mtr.	90			
4	Supply, installation, testing & commissioning of 25 X 3 mm GI flat for earthing of equipment and pannels including making and termination required complete as perdirection of Engineer-in-charge.	Mtr.	100			
5	Supply of materials installation, testing & commissioning of GI cable tray (Ladder type)for lying of cable to provide power supply for hoist and gantry side, made out of GI as per direction of Engineer-in-charge.	Mtr.	100			
6	Supply, installation, testing & commissioning of 3 mtr. Long copper earthing electrode 40 mm dia MTB PC earthing device conforming to IS:3043, digging earth pits and filling with chemical compound (Earth resistance improvement compound) and making earth chamber as per direction of Engineer-in-Charge.	Nos	2			

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project,

7	Supply of materials, installation, testing & commissioning of 100mm dia GI pipe with bend for pier lower position to upper part pier position top to complete as per direction of Engineer-in-charge.	Mtr.	15			
8	Supply of materials, installation, testing & commissioning of GI double lock "C" clamp accompanied through cable and should be connected to earthing points, as required and as per the direction of Engineer-in-charge.	Nos	80			
9	Supply of materials, installation, testing & commissioning of 8 nos. GI SWG wire as required and as per the direction of Engineer-in-charge.	Mtr	100			
10	Supply, installation, testing & commissioning of limit switches shall be rated as 16 Amp at 440Volt AC, 50 Hz and of direct position action type and as per direction of Engineer-in-Charge (Position Indicator).	Set	08			
11	Supply, delivery, installation, testing & commissioning of 1 x 120-Watt LED street light fixture with all accessories including power factor improvement condenser & making connection including 08 Ft. Long tubular GI pole fixed on the top of the hoist bridge and flexible cables for JB including 10 Amp SP MCB to the fixture as required and as per the direction of Engineer-in-Charge.	Set	02			
			TOTAL			

Signature of the "Tenderer or his/their power of attorney holder with name, date and seal

,

Senior Manager (Mech.),OCCL
Kanupur Gate Erection Project,